

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/24/2017-18, Date: 21.02.2018

Providing and Laying PVC pipelines and additional GI Pipes and Pump and Motors to existing borewells in Ward no. 06 Byatarayanapura Sub division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				H V Nagaraj	
				In Figures	In Words
1	2	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings17.50 HP 30 stage (P.NO-XXXXIII, I.NO-33, PWD SR 16-17)	No	70685	Rupees Seventy Thousand Six Hundred Eighty Five Only
2	800	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc.. complete 'A' grade(excluding cost of fittings)b50mm dia GI pipe (SR 16-17 PWD, P.No.XVII Sl.no. 509)	Rmtr	340	Rupees Three Hundred Forty Only
3	110	Providing & fixing heavy duty collar (P.NO-III, I.NO-86, PRED 12-13 SR)	No	159	Rupees One Hundred Fifty Nine Only
4	2000	Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia (P.NO-535, I.NO-30 (c), BWSSB 12-13 SR)	Mtr	164	Rupees One Hundred Sixty Four Only
5	10	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc.. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	No	14800	Rupees Fourteen Thousand Eight Hundred Only
6	220000	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc.. complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm	0.34	and Thirty Four Paise Only
7	30	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. (PWD SR 16-17, P.NO.XXIII, Sl.no, 659)	No	1282	Rupees One Thousand Two Hundred Eighty Two Only
8	75	Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline. 50mm dia (PWD SR 16-17, P.NO.XXIV, Sl.no, 673) .	No	1749	Rupees One Thousand Seven Hundred Forty Nine Only
9	44	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)	No	906	Rupees Nine Hundred Six Only

Signature of the contractor

Page 1 of 2

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				H V Nagaraj	
				In Figures	In Words
10	150	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3b KPWD Electrical SR 2010-11	No	150	Rupees One Hundred Fifty Only
11	25	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc, (P.NO - 555, I.NO - 16 (b) , BWSSB SR 13-14)	No	271	Rupees Two Hundred Seventy One Only
12	25	Supplying shunt capacitor's confirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating No's. (MR)	No	1350	Rupees One Thousand Three Hundred Fifty Only
13	24	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc., Complete. 50mm dia (P.NO - 103, I.NO - 13.79.6, PWD SR 13-14)	No	1515	Rupees One Thousand Five Hundred Fifteen Only
14	533.25	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 5, I.NO - 2.3, PWD SR 16-17)	Cum	142.4	Rupees One Hundred Forty Two and Forty Paise Only
15	1185	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 16-17)	Mtr	356	Rupees Three Hundred Fifty Six Only
16	533.25	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 6, I.NO - 2.11, PWD SR 16-17)	Cum	53.4	Rupees Fifty Three and Forty Paise Only
17	26	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 97 / I.13.37 PWD SR - 2016-17	Each	2100	Rupees Two Thousand One Hundred Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/07